

SEALED PROPOSALS FOR BUILDING CONDITION ASSESSMENTS WILL BE RECEIVED BY:

The Corporation of the Municipality of Powassan 250 Clark Street, PO Box 250 POWASSAN, ON, POH 1Z0

REQUEST FOR PROPOSAL NUMBER: 2020-04

BUILDING CONDITION ASSESSMENTS

TENDER CLOSING DATE AND TIME:	2:00 P.M. LOCAL TIME May 19, 2020
TENDER OPENING TIME:	2:30 P.M. LOCAL TIME May 19, 2020 To be awarded at the council meeting of May 19, 2020
QUOTE FOR:	Building system inspections, report, a

Building system inspections, report, and recommendations for Powassan Arena's.

This complete RFP package must be submitted in a sealed envelope, clearly marked "Building Condition Assessments RFP: 2020-04" LOWEST OR ANY QUOTE NOT NECESSARILY ACCEPTED

Location Of Work:

The location of work is to be: The Sportsplex arena (433 Main Street, Powassan), the Trout Creek Community Center (181 Main Street West, Trout Creek), and the Public Works Sand Dome (750 Main Street, Powassan) as described in the bid form.

Schedule of Contract Documents:

- 1. The following information for bidders
- 2. Bid Form
- 3. Appendix A Proposal Evaluation
- 4. Appendix B Previous Building Condition Assessment
- Standards: OPSS.MUNI 100, and Structural Condition Assessments of Existing Buildings and Designated Structures Guideline (2016) – PEO. These are **not** attached to this proposal; however, the successful service provider is expected to read these in their entirety.

General Information:

All inquiries concerning the proposal, prior to proposal closing shall be directed to:

Codey Munshaw EIT, Public Works Engineer Municipality of Powassan Box 250, 250 Clark Street, Powassan ON POH 1Z0 Telephone 724-2813 ext. 202 or 705-491-1749/Fax 724-5533 Email: <u>cmunshaw@powassan.net</u>

Mark Martin, C.B.O (Chief Building Officer) Municipality of Powassan Box 250, 250 Clark Street, Powassan ON P0H 1Z0 Telephone 724-2813 ext. 228 or 492-3488 Email: <u>mmartin@powassan.net</u>

For the purpose of this document a company providing inspection services for the Municipality of Powassan, will hereby be referred to as a "Service Provider".

The Service Provider will submit their sealed proposal's by traditional mail/drop-off at the previously stated Municipal building before RFP closure. In light of the COVID-19 pandemic, the Municipality will also accept proposals via. email (in PDF format **only**) at <u>cmunshaw@powassan.net</u>, or by fax at 705-724-5533. We encourage all interested parties to use these alternative submission methods (if faxed or emailed, bid deposits shall be mailed via traditional mail, with a copy of the bid deposit attached to the faxed/emailed Proposal Submission). Service Provider must submit this entire completed proposal package (excepts Appendix A, which will be completed by Municipal staff).

A Service Provider may amend their proposal at any time prior to the set closing date/time by submitting a signed and sealed amendment. No amendments will be accepted post RFP closure. A proposal may be voided by superseding it with a later proposal or letter of withdrawal, prior to the closing date and time.

Any and all RFP's that are received after the quote closing date/time, will be rejected by the Municipality. Any and all unsigned Tenders will be deemed unacceptable, and will be rejected by the Municipality.

Notification of Acceptance of proposal will be by telephone and written form of notice, to the address of the Contractor used on the bid forms. The Date of Acceptance shall be deemed to be the date the Contractor receives the Notification of Acceptance.

Due to the COVID-19 precautions taken by the Municipality, the proposal opening process will **not** be open to the public. The bid results will be posted on the Municipal website following the Tender opening.

Scope of Work:

The Service Provider will be responsible for the supply of all necessary manpower to generate a building condition assessment for the following buildings:

- Powassan Sportsplex (433 Main Street, Powassan): This building is approximately 37,650 ft², and serves as an arena and curling rink.
- Trout Creek Community Center (181 Main Street West, Trout Creek): This building is approximately 28,330 ft², and serves as an arena and a community centre.
- Public Works Sand Dome (750 Main Street, Powassan): This building is approximately 6,628 ft², and is used to store the Municipality's winter sand.

The primary goal of this work is to identify any potential issues with these facilities to ensue that they are safe for the employees/general public, and that any required repairs that could compromise the safety of the employees/general public can be made in a timely manner. The secondary goal of this work is to identify any necessary repairs required to be made to the: foundation, exterior walls, interior walls, roof and roof framing, grandstands and or bleachers, interior floors, mechanical and electrical systems, and arena systems.

Project Details:

The Service Provider shall conduct a close-up/comprehensive examination of all exposed components of the roof and framing members of the Sportsplex, T.C.C.C (Trout Creek Community Center), and Public Works Sand Dome. The condition of the materials will be checked and the extent of deterioration will be recorded. The Service Provider shall also assess all major building components, and evaluate the current condition as well as, provide suggested future rehabilitation/replacement strategies. It is assumed that the Municipality shall supply all necessary ladders and lift equipment upon the Service Provider request.

The Service Provider shall conduct a structural review of the existing building components and/or review of previous Inspection Reports and drawings to confirm the adequacy of the building with respect to current requirements of the Ontario Building Code. Previous inspection reports and available building drawings shall be provided at the Service Providers request. The Service Provider shall also use the November 2016 "Structural Condition Assessments of Existing Buildings and Designated Structures Guideline" published by P.E.O (Professional Engineers Ontario) as a guideline for conducting the condition assessments.

The Service Provider shall prepare a Building Condition Assessment for each building summarizing all observations, conclusions and recommendations. This will also include a recommended interval for future inspections. The Service Provider shall provide individual reports for each building inspected.

The successful service provider shall supply to the Public Works Engineer three (3) sets of paper copies (each facility shall have its own separate report), and one (1) set of the digital copy of the final structural/condition assessment. The digital copy shall be in PDF format, and shall be displayed in such a manner so that this information can be easily transferred into the Municipality's asset management software.

The Municipality requires all interested parties to provide two different Prices: **Option A**: shall include all items as stated above and as shown in Appendix B-Previous Building Condition Assessment.

Option B: Shall include all of the above mentioned items, as well as an asset management plan/table for these buildings. This asset management plan will consist of a table providing rough estimates of all building repair costs, and shall prioritize these cost. This plan will lay out what spending is required every year for a ten (10) year period. This table should also include an estimated remaining useful life of all inspected items.

Proposal Evaluation Criteria:

This proposal will be evaluated based on the evaluation criteria seen on page 5 in Figure 1. We ask that a brief description of the work plan, timeline, the equipment to be used, equipment required to be supplied by the Municipality, the manpower proposed, and references of other similar projects completed in the past be included with the proposal.

Start date for the work will be mutually agreed upon by both parties, and will be completed as per the Service Provider's proposal timeline.

The submitted proposal will be evaluated by the Municipality of Powassan as per figure 1: evaluation criteria. The Municipality will base the award selection on the overall evaluation score of the proposals, recommending that council awards the contract to the Service Provider with the overall highest evaluation score.

Item	% Of Overall Evaluation Score
Timeline	10%
Quality of submission package	10%
Work related experience	20%
Pricing	60%

Figure 1: Evaluation Criteria

Provisional Items:

Items of work that may be required during the course of this project, but the exact requirements of which will depend on budget compatibility, are shown as "Provisional Items". The Service Provider shall price these items accordingly and shall not claim any anticipated loss of profit or increased overhead if any or all of these items are reduced or deleted altogether. These items will depend in large part on the service provider requirements to properly inspect these structures (for instance, the sand dome is partially filled with winter sand, and salt. If the service provider needs this structure to be empty, the Municipality may elect to remove this item altogether).

Liability/Indemnification:

The Contractor shall indemnify the Municipality, its officers, employees and agents from all claims, demands, actions, or other proceedings initiated by others arising out of or attributable to anything done, or omitted to be done by the Contractor, its officers, employees or agents in connection with the services performed or required to be performed under this Contract.

Liability/Insurance:

The Service Provider shall maintain a policy of motor vehicle liability insurance for both owned and non-owned licensed vehicles having limits of not less than five million dollars (\$5,000,000.00) inclusive per occurrence for bodily injury, death, and damage to property.

The Service Provider shall maintain a policy of general liability insurance having limits of not less than five million dollars (\$5,000,000.00) inclusive per occurrence for bodily injury, death, and damage to property.

The general liability policy shall include the Municipality as an additional insured, but only in respect of and for the duration of the services to be performed under this contract and shall contain a cross liability clause endorsement.

The Service Provider shall also maintain professional liability (errors and omissions) insurance in the amount of five-hundred thousand dollars (\$500,000.00) per claim and one-million dollars (\$1,000,000.00) in aggregate. This insurance shall cover any and all errors or omissions made by the professional in the rendering of all reports and professional services as requested by this proposal.

The Service Provider shall provide proof of valid WSIB coverage. Prior to the beginning of the Contract the Service Provider must provide proof of insurance

 (certificate of insurance or certified copy of policy) to the Public Works Engineer.

 POLICY NO.:
 INSURANCE CO.:

 POLICY NO.:
 INSURANCE CO.:

 AMOUNT:
 EXPIRY DATE:

Bidder Deposit:

Bidders are required to deposit a certified cheque, payable to the Corporation of the Municipality of Powassan for 10% of the total bid price. Unsuccessful bidders' cheques will be returned within thirty (30) days following the contract award. The successful bidder's cheque will be released when all necessary documents have been received by the Municipality.

Payment, Holdback, and Completion:

The Service Provider shall be paid in full, at the bid unit price for all completed building condition assessments supplied to the municipality, upon successful completion of the contract to the satisfaction of the Municipality. Any change in the proposed unit bid price must be approved by the Public Works Engineer.

Breach of Contract and Contract Termination:

If the Contractor or Municipality shall fail to meet the terms of the contract herein explained, the party conforming to the contract will have the opportunity to terminate the contract due to the other party breaching the contract. When a non-conformance is noticed by a party, the conforming party has a responsibility to notify (either by letter or email) the non-conforming party. The non-conforming party will have 10 business days to meet the terms of the contract, failure to do so will be a breach of contract and will be grounds for immediate dismissal.

Additionally, should the Contractor or Municipality knowingly provide false information during the completion of this contract document, it will be henceforth considered that the complying party was given insufficient information to formal accept the contract; meaning that the contract will be now in void, unless both parties can agree on new terms to this contract.

Health & Safety:

All work performed under this Contract must be carried out in accordance with the Municipality's Health and Safety Policy and any federal and provincial health and safety legislation and regulations. Failure to comply with this condition will be considered a breach of contract.

It will be the responsibility of the Service Provider to ensure: that all employees/workers conducting building assessments wear all appropriate PPE (Personal Protective Equipment), all regulations and procedures within the Occupational Health and Safety Act are met, that the health and safety of all workers or employees is protected, and that the health welfare and property of all residents/civilians is preserved.

Any and all unsafe acts committed during the completion of this contract, shall be brought to the attention of the operations manager who shall notify the on-site foreman. If the occurrence/act is not rectified in a timely manner, the Ministry of Labour will be informed.

Bid Form

The Service Provider has carefully examined the conditions and specifications attached and referred to in this contract, and has carefully examined the site and work location and understands and accepts the said conditions and specifications, and for the prices set forth in this quote, hereby offers to furnish all labour, equipment and materials, except as otherwise specified in the contract, to complete the work in strict accordance with said conditions and specifications for the sum provided in the table below:

Item	Spec	Description	Floor Area	Units	Unit Bid Price	Total Bid
		Option A – Sta	ndard Repor	ts		
1	OPSS 206,OPSS 1010, S.P.	Sportsplex Arena	37,650	ft²	\$	\$
2	OPSS 206,OPSS 1010, S.P.	Trout Creek Community Centre	28,330	ft²	\$	\$
		Provisio	nal Item			
3	OPSS 206,OPSS 1010, S.P.	Public Works Sand Dome	6,628	ft²	\$	\$
				HST	\$	
				Total Bid	\$	

Item	m Spec Descript		Floor Area	Units	Unit Bid Price	Total Bid
	Optio	n B – Reports With	Asset Manag	ement Tabl	e	
1	OPSS 206,OPSS 1010, S.P.	Sportsplex Arena	37,650	ft²	\$	\$
2	OPSS 206,OPSS 1010, S.P.	Trout Creek Community Centre	28,330	ft²	\$	\$
	· · ·	Provisio	nal Item		•	
3	OPSS 206,OPSS 1010, S.P.	Public Works Sand Dome	6,628	ft²	\$	\$
				HST	\$	
				Total Bid	\$	

Bid Form

I/We (the Service Provider) promise that: I/we are over the age of 18, are of right mind, are not under the influence of alcohol or controlled substances, wish to enter into a legally binding contract with the Municipality of Powassan, and agree to perform the work without undue delay to ensure that work is completed as specified in this RFP.

Name of Individual or Firm hereinafter referred to as the "Service Provider" (Print) Address:		
	-	
Phone Number	_	
Authorized Signature		-
Title		
Date		
Witness or Firm Seal		



(To be completed by Municipal Staff)

<u>.</u>

Service Provider:

Date:

•

	Timeline	
Score (of 5)	Description	Service Provider Score (Place an "X" in the row corresponding to Service Providers Score)
5	Service Provider submitted fastest feasible timeline	
4	Service provider submitted a timeline that is up to 5% longer than quickest timeline, or second fastest timeline	
3	Service Provider submitted a timeline that is 5% to 10% longer than quickest timeline, or third fastest timeline	
2	Service Provider submitted a timeline that is 10% to 15% longer than quickest timeline, or fourth fastest timeline	
1	Service Provider submitted a valid proposal, however the proposed timeline is greater than 15% longer than quickest proposed timeline, or is slower that fourth fastest timeline	
0	Service Provider did not provide a valid quote in accordance to RFP document, did not include this section, or timeline is deemed not to be feasible/acceptable.	
	Quality of Submission Package	
Score (of 5)	Description	Service Provider Score (Place an "X" in the row corresponding to Service Providers Score)
5	Service Provider submitted proposal of the highest quality	
4	Service Provider submitted proposal of the second highest quality	
3	Service Provider submitted a proposal of the third highest quality	
2	Service Provider submitted a proposal of the fourth highest quality	
1	Service provider submitted a proposal of quality lower than fourth highest, or proposal was of subpar quality. (note: placement of proposal quality does not guarantee a higher score if it is deemed that the proposal is of subpar quality)	

0	Service Provider did not provide a valid quote in accordance to RFP document, or did not include this section	
	Work Related Experience	
Score (of 10)	Description	Service Provider Score (Place an "X" in the row corresponding to Service Providers Score)
10	Service Provider submitted quality references , and proof of project completion well above the scope of work stated in the RFP package	
8	Service Provider submitted quality references, and proof of project completion of a similar scope of work to the RFP package	
6	Service Provider submitted references, and proof of project completion that satisfies the Municipality in the capability of the Service Provider completing the contract effectively	
4	Service Provider submitted poor references, and did not provide the Municipality adequate proof of project completion that would indicate that the Service Provider could effectively preform the work required	
2	Service Provider submitted very poor or no reference, and submitted proof of project completion of a scope well below the scope of work specified in the RFP package. Service Provider has not yet completed a project of this magnitude, and the Municipality does not believe that the service provider can conduct the required work effectively.	
0	Service Provider did not provide a valid quote in accordance to RFP document, did not include this section, or work related experience is deemed not to be acceptable.	
	Pricing	
Score (of 30)	Description	Service Provider Score (Place an "X" in the row corresponding to Service Providers Score)
<u> </u>	Service Provider submitted cheapest feasible quote Service provider submitted a quote that is up to 5% more expensive than the cheapest quote, or submitted the second cheapest quote	
20	Service Provider submitted a quote that is 5% to 10% more expensive than the cheapest quote, or third cheapest quote	

15	Service Provider submitted a quote that is 10% to 15% more expensive than the cheapest, or fourth cheapest quote					
10	Service Provider submitted a quote that is 15% to 20% more expensive than the cheapest quote, or quote is the fifth cheapest					
5	Service Provider submitted a quote that is greater than 20% more expensive than the cheapest quote, or quote is the sixth cheapest					
0	Service Provider did not provide a valid quote in accordance to RFP document, Service Provider did not include this section, an error was found in the bid costing, or the quote price was deemed not to be acceptable					
	Total Service Provider Score (Combined Score For All Categories)					
	Score (of 50)					

Note: Throughout the evaluation, the Municipality of Powassan has the right to select evaluation score based on either percentage (%) more that the lowest or ranking (in the pricing and timeline categories), if the Municipality deems it necessary for the proposal selection. The Municipality might choose to use this technique if there is a tie, and one company did not perform adequately on some evaluation categories.

As a default the Municipality of Powassan shall evaluate the Service Providers proposals by means on ranking (i.e.: first, second, third, etc.) for pricing and timeline categories.

The proposal evaluation will be completed after bid opening on May 19, 2020. Upon the completion of the proposal evaluation, the evaluation scores will be compared. The Service Provider that submitted the proposal with the highest overall score will be recommended to council, to have their proposal accepted.

Municipality of Powassan

POWASSAN SPORTPLEX BUILDING CONDITION ASSESSMENT

TSH PROJECT NO. 36-19660

RECEIVED

Municipality of Powessar



copy: Mayor and Council Members Sportsplex Board of Management



TABLE OF CONTENTS

.0	INTRODUCTION
	.0

2.0 BUILDING CONDITION ASSESSMENT

APPENDIX A SITE PHOTOS

BUILDING CONDITION ASSESSMENT POWASSAN SPORTPLEX

1.0 INTRODUCTION

Totten Sims Hubicki Associates have been commissioned by the Municipality of Powassan to complete a Building Condition Assessment of the Powassan Sportplex. The building assessment were completed to meet the Ministry of Labour requirements and Guidelines for the Investigation and Repair of Arena Structures (A.P.E.O. 1971) as well as to investigate interior and exterior building components for deteriorations and possible problem areas requiring maintenance.

It is understood that the existing arena structural components have been checked and verified to have been designed to meet the requirements of the 1970 National Building code or later editions.

Recommendations for restoration or upgrade items are identified and prioritised with respect to the time frame for completing the work.

Site photographs are included in Appendix

2.0 BUILDING CONDITION ASSESSMENT

BUILDING	COMPONENT	P	REMARKS	REPAIR PRIORIT
Site	Asphalt	-	Asphalt areas appear to be in fair condition	
Foundation	Concrete		There is no evidence of any foundation settlements or	
	Block		detrimental movements.	
			Extensive moisture and unsightly algae growth along the north	1-2 years
			exterior foundation wall indicates a lack of perimeter	
			insulation. It is recommended that the exterior grades be	
			raised not only to eliminate the exposed walls but also to	
			reduce the step to the exit doors from the facility.	
Exterior	Metal Siding		The exterior metal siding is in fair to good condition.	
Walls			All wall penetrations should be properly sealed to prevent	Immediate
			moisture infiltration.	
	Masonry		Most of the painted exterior masonry was noted to be in good	
			condition.	
		٠	There is no evidence of settlement or movements with the	
			back up load bearing masonry block.	
		=	Parging in several areas is delaminated due to frost action.	
	Control Joints		The existing caulked control joints are in fair condition but	3-5 years
			will need to be restored in 3 years	
Interior	Concrete		All interior walls appeared to be in good condition.	
Walls	Block			
Roof	Steel Frames		The main steel roof frames are in good condition.	
Framing		•	All joists appeared to be straight and true with no signs of	
			excessive deflections or deteriorations.	
		•	Welds within the joists all appear in good condition.	
		•	Minor corrosion of the bottom chord of the joists was noted. It	3-5 years
			is recommended that the joists be re-painted within Re-painted	
			within 3 to 5 years to prevent excessive rust build up and	
			costly cleaning in the future. Refer to photo	
	Connections		Connections to the exterior masonry were found to be in good	

BUILDING	COMPONENT		REMARKS	REPAIR PRIORITY
			condition with no signs of distress of deterioration.	
	Bridging		Steel framing elements appeared to be in good condition.	
	Purlins		The cold formed Z purlins are in fair condition and have	3-5 years
			moderate surface corrosion. The purlins should be painted	
			within 5 years	
	Roof / Wall		Roof and wall brace rods were noted in good condition. Rod	
	Bracing		tension was generally found to be acceptable.	
	Frame	•	The galvanized brace angles are in good condition.	
	Bracing			
	Timber roof	•	There was no evidence of material distress on the existing	
	trusses		trusses.	
Roofing	Roof Deck		The pre-finished standing seam metal roof deck was noted in	
	Arena		fair to good condition. Minor corrosion was observed. Refer	
			to photo.	
	Roof Deck	•	The mechanically fastened pre-finished roof deck is in fair	Immediate
	Zamboni		condition but requires repairs to several leaks. It is	
			recommended that all fasteners be torqued and sealed to	
			prevent further corrosion and leakage. Refer to photo.	
	Roof		The existing foil faced batt insulation is in fair condition.	
	insulation	•	Significant corrosion was noted on the wire mesh used to	
			support the insulation. Painting of the wire mesh is	
			recommended as soon as possible for aesthetic reasons.	
	Shingles	•	The existing roofing shingles on the east end of the facility are	
			in fair condition. Significant deterioration was noted on local	
			areas of the roof near the chimney stack, eaves and ridge.	
			Refer to photos.	
		•	Replacement of local areas of shingles is recommended within	2-4 years
			2 to 4 years.	j
	Low Emissive		There is no low-Emissive ceiling in the facility.	
	Ceiling	•	The installation of a low E ceiling is recommended to reduce	
			the rate of deterioration and corrosion of the roof steel	
			elements.	
Grandstand	Pre-cast	•	There was no significant deterioration or distress apparent on	
	Concrete		the viewing area support slabs and support framing.	

BUILDING COMPONENT REMARKS

				PRIORI
	slabs			
Interior	Steel /		There was no evidence of significant material deterioration or	
Floors	Concrete		distress on the interior elevated floor framing systems.	
	Hall / Kitchen		The existing hall and kitchen finishes are in fair to good	
			condition.	
		•	The existing thermopane windows appeared in good	
			condition.	
	Dressing		The existing dressing rooms are in fair condition.	
	Rooms		Fresh air louvers to the exterior or to the interior corridor	Immediate
			should be provided to allow the exhaust system to function.	
			The T-bar ceiling was damaged in several areas.	
			The showers are in fair condition and appear to have been	
			recently painted.	
	Washrooms		The existing washrooms are not barrier free.	
		•	Consideration should be given for the upgrade of the facility	
			to allow better barrier free access.	
	Office		The existing carpeting in the office area is in poor condition	
			and should be replaced.	
	Curling Club		The existing curling club finishes are in good condition.	
	Rubber	•	The existing rubber flooring in the lobby, washrooms and	
	Flooring		dressing rooms was noted in fair to good condition.	
			Areas should be replaced as required.	
	Doors and	•	The interior and exterior metal doors are generally in good	
	Hardware		condition.	
		•	The interior wood doors to the men's washroom is in poor	
			condition and should be replaced.	
Irena	Dasherboards		The existing dasherboards are constructed using steel posts	
			and wood stringers. The boards are in fair to good condition	
			with only minor adjustments needed on gate hardware.	
			The monofilament netting meets current codes and is in good	
			condition.	
		•	The lift gate framing and bracing elements were under repair	
			at the time of investigations. TSH would recommend that the	
			lift gate be replaced with a swing gate for improved safety.	

REPAIR

4

BUILDING	COMPONENT		REMARKS	REPAIR PRIORITY
			The gate would need to be constructed in two sections. The	
			upper part of the gate would be a swing gate, while the lower	
			8" +/- section would be removable (drop in panel) in order to	
			accommodate the ramp in the floor.	
	Rink slab		The existing concrete rink slab is in good condition with only	
			minor surface cracking. There is no remedial work required at	
			this time.	
	Arena	•	The existing infra-red heaters were reported to be in good	
	Heaters		condition.	
	Arena		The one 7.5 ton mechanical dehumidifier was reported to be	2-5 years
	Dehumidifier		about 15 years old and is reaching its life expectancy.	·
			Replacement may be required within 2 to 5 years	
		•	Considerations should also be given for the installation of one	
			addition unit to better maintain relative humidity especially	
			during the fall start up months.	
	Zamboni	•	The Zamboni room should be provided with a propane gas	Immediate
	Room		leak detector for safety. The gas fired hot water heater and	
			boiler are slightly elevated but would be an ignition source	
			should there be a gas leak from the Zamboni.	
		•	Exhaust ventilation of the large snow pit should also be	
			installed to prevent the accumulation of propane at low levels.	
		•	The current wooden door to the arena should be replaced with	
			a rated fire door to meet current building codes.	
	Refrigeration	•	The existing refrigeration room is in fair condition.	
	Room	8	The exposed rigid wall insulation must be covered with	
			drywall to meet building codes and reduce smoke	
			development should there be a fire.	
		•	A fresh air intake louver should be installed to allow the	
			exhaust system to properly function.	
	Refrigeration	•	The refrigeration system is about 30 years old and is reaching	
	System		its life expectancy. The system consists of 2 - 50 HP mycom	
			compressors, shell and tube chiller, brine pump and induced	
			draft evaporative condenser.	
		-	It is recommended that the ammonia side of the system be	3-5 years

BUILDING	COMPONENT	REMARKS	REPAIR PRIORITY
		replaced within 3 - 5 years and be upgraded with new energy	
		efficient control technology.	
		• The existing brine pump base is deteriorated and should be	1 year
		repaired as soon as possible.	·
	•	The steel water tank is badly rusted and should be changed	2-3 years
		within 3 years.	2
	•	Compressor cooling is achieved by a once through water	
		system which wastes extensive amounts of water. It is	
		recommended that a closed loop glycol cooling system be	
		installed when major upgrades are considered on the plant.	
	Heating •	The existing domestic hot water heating system and hot water	
	System	building heat is oil fired and has reached its life expectancy.	
	•	It is recommended that the mechanical systems be converted	1-3 years
		with natural gas fired units to match the rest of the facility.	
Electrical	Power •	The existing 600 amp 600V and 100amp 240 V electrical	
System		services are in good condition.	
	•	The use of two services for one building is not a preferred	
		system due to the safety concerns. Extreme care should be	
		taken when any repairs or modifications are undertaken.	
	Lighting •	The existing rink lighting is adequate and provided by metal	
		halide units. Regular replacement of bulbs are required as the	
		light levels degrade over time.	
	•	The existing florescent light fixtures with T12 lamps should	
		be converted to T8 for energy savings.	

3.0 STRUCTURAL ASSESSMENT

This inspection of the Powassan Sportplex was completed in accordance with the Ministry of Labour requirements and Guidelines for the Investigation and Repair of Arena Structures (A.P.E.O. 1971). It is understood that since the Arena was previously inspected and upgrades completed as well as evaluated with respect to the design requirements of the 1970 National Building Code, a detailed structural analysis has not been completed at this time.

Based on our visual inspection and structural review of the components of the Arena, it is concluded that the existing structure is in good condition and adequate to support the loading as specified by the Ontario Building Code at time of construction and at least the 1970 National Building Code.

Recommendations with regard to maintenance items should be addressed in order to extend the life expectancy of the facility.

It is recommended that a future structural inspection of the arena be carried out in Five (5) years.

PREPARED BY:



BUILDING CONDITION ASSESSMENT POWASSAN SPORTPLEX

APPENDIX A

SITE PHOTOGRAPHS

BUILDING CONDITION ASSESSMENT POWASSAN SPORTPLEX



EAST ELEVATION

Note: General Condition



NORTH ELEVATION Note: Condensation on foundation wall



VIEW OF ROOF DECK

Note: Minor corrosion



VIEW OF ROOF Note: Deterioration of shingles at ridge and eave



INTERIOR LOBBY

Note: General Condition



VIEW OR ARENA ROOF DECK

Note: Corrosion of wire mesh

BUILDING CONDITION ASSESSMENT POWASSAN SPORTPLEX



INTERIOR VIEW OF REFRIGERATION ROOM Note: Exposed wall insulation



INTERIOR VIEW OF DASERBOARD LIFT GATE

Note: General condition and support framing